



Lead Plan Review for Demolition

Start and anticipated completion time of project

Start and end of work time each day

Adhere to the City of Stamford Noise Ordinance

Explanation of construction debris removal

Supply lead abatement plan as guideline if needed

Provide lead waste removal and storage location until work is completed if needed

Provide rat/rodent control measures prior, during and after demolition

Provide plan if structure is pre-1978 for interior and exterior precautionary dust control measures when working on surfaces that may contain asbestos/lead to prevent exposure by dust, air or waste water contamination

Provide Lead pamphlet and RRP Booklet

Provide notification to surrounding properties that demolition of structure contains lead and proof of services to residents receiving information

Dust control measures must be set up to limit exposure from any potential environmental hazards during demolition work to surrounding occupied structures

Identify CT licensed contractor that will provide oversight of lead removal

Requirements listed above must be provided before a health department approval is granted

Lead/Environmental soil contaminate testing must be conducted after the demolition of the property and the results must be sent to the Health Department for review

A conditionally approval status will be granted but may be withdrawn if all requirements are not met and a final CO signoff will not be obtained from the Health Department. Please note that depending on the scope of work and age of structure all listed requirements may not be needed.